


1 B1 EGRESS PLAN  
SCALE: 3/32"=1'-0"

	ALLOWED	PROPOSED
MAXIMUM EXIT TRAVEL DISTANCE (T) IBC 2012 TABLE 1016.2	200'	141'-11"
MAXIMUM COMMON PATH OF TRAVEL DISTANCE (l) IBC 2012 TABLE 1014.3	100'	80'



OCCUPANT LOAD B1	MIN. EGRESS WIDTH REQUIRED	MIN. EGRESS WIDTH PROPOSED
B - ADMINISTRATION: 493sf/100= 5 PEOPLE S-2 - MECH/STORAGE: 2987sf/300= 10 PEOPLE		
TOTAL = 15 PEOPLE x .2" = 3"	3"	36"



2 FIRST FLOOR EGRESS PLAN  
SCALE: 3/32"=1'-0"

	ALLOWED	PROPOSED
MAXIMUM EXIT TRAVEL DISTANCE (T) IBC 2012 TABLE 1016.2	200'	101'-6"
MAXIMUM COMMON PATH OF TRAVEL DISTANCE (l) IBC 2012 TABLE 1014.3	75'	54'-3"
REOTENESS - IBC 2012 1015.1; (d) > (D)/2	D/2=50'-2"	d=80'-2"

OCCUPANT LOAD 1ST FL	MIN. EGRESS WIDTH REQUIRED	MIN. EGRESS WIDTH PROPOSED
A-3 - ASSEMBLY: SANCTUARY 1969sf/7= 281 PEOPLE PULPIT+ALTAR 773sf/15= 52 PEOPLE PEWS (9'0"x16) = 72 PEOPLE PEWS (6'0"x4) = 12 PEOPLE S-2 - MECH/STORAGE: 130sf/300= 1 PERSON		
TOTAL = 418 PEOPLE x .2" = 84"	84"	152"



3 SECOND FLOOR EGRESS PLAN  
SCALE: 3/32"=1'-0"

	ALLOWED	PROPOSED
MAXIMUM EXIT TRAVEL DISTANCE (T) IBC 2012 TABLE 1016.2	200'	38'-2"
MAXIMUM COMMON PATH OF TRAVEL DISTANCE (l) IBC 2012 TABLE 1014.3	75'	27'-1"

OCCUPANT LOAD MEZZANINE	MIN. EGRESS WIDTH REQUIRED	MIN. EGRESS WIDTH PROPOSED
A-3 - ASSEMBLY: 317sf/7= 45 PEOPLE S-2 - MECH/STORAGE: 206sf/300= 1 PERSON		
TOTAL = 46 PEOPLE x .2" = 9"	9"	36"




Architect  
Delizzo Sellgson Architects  
Delizzo Architects & Planners P.C.  
T: (301) 424-8944  
delizzoarch@aol.com

civil  
Macris, Hendricks and Glascock, P.A.  
T: 301.670.0840

mep  
AC-DC ENTERPRISE LLC  
T 703.944.6146

structural  
A+F Engineers  
T 202.628.1600

St Andrew Church  
9111 River Road  
Potomac MD 20854



ISSUE	
PERMIT SET	03.31.2020

Professional Certification.  
I hereby certify that these documents were prepared or approved by me, and that I am a duly licensed architect under the laws of the State of Maryland.  
License No.: AS116  
Expiration Date: 02.24.2021  
© 2019 st andrew church space shop LLC  
This project is protected by copyright laws and international treaties.

EGRESS  
PLANS

DATE  
SCALE AS NOTED

A005